



- A. ALL DATA OUTLETS, AND TELE/DATA OUTLETS THIS SHEET SHALL BE MOUNTED 48" AFF TO CENTER.
- B. DO NOT MOUNT BOXES BACK TO BACK BETWEEN ROOMS. OFFSET BOXES TO IMPEDE SOUND TRANSMISSION.
- C. ALL CONSTRUCTION SHALL CONFORM TO CURRENT AMI-400 DIVISION 27 STANDARDS.

KEYED NOTES: □

- 1. (1) CAT 6 CABLE, 1"C
- 2. (2) CAT 6 CABLES, 1"C.
- 3. PROVIDE 1" EMPTY CONDUIT WITH PULLSTRING IN ADDITION TO CONDUIT WITH CABLING.
- 4. (4) CAT 6 CABLES, 1"C.
- 5. PROVIDE 1 1/4" EMPTY CONDUIT WITH PULLSTRING IN ADDITION TO CONDUIT WITH CABLING.
- 6. (6) CAT 6 CABLES, 1"C.
- 7. 18"W X 18"L X 6"D SCREW COVER PULL-BOX MOUNTED IN STRUCTURE OR ABOVE CEILING.
- 8. (8) CAT 6 CABLES, 1"C.
- 9. TELEPHONE TERMINAL BOARD "TTB." LINE WALLS OF ENTIRE ROOM WITH 3/4" FIRE-RETARDANT PLYWOOD COATED WITH FIRE-RETARDANT PAINT FROM FLOOR TO CEILING WITH NO MORE THAN 1/2" GAPS BETWEEN PLYWOOD SHEETS.
- 10. (10) CAT 6 CABLES, 1 1/4"C.
- 11. PROVIDE (1) CISCO #3750X NETWORK SWITCH AND (1) POWER OVER ETHERNET 24 PORT POE.
- 12. DATA OUTLET MOUNTED ABOVE ACCESSIBLE CEILING (UNLESS NOTED OTHERWISE) FOR FUTURE WIRELESS ACCESS POINT. COORDINATE EXACT QUANTITY AND LOCATION WITH AMI-400.
- 13. (3) CAT 6 CABLES, 1"C.
- 14. MOUNT TO STRUCTURE.
- 15. (5) CAT 6 CABLES, 1"C.
- 16. (7) CAT 6 CABLES, 1"C.
- 17. (9) CAT 6 CABLES, 1 1/4"C.
- 18. (11) CAT 6 CABLES, 1 1/4"C.

REES ASSOCIATES INC

ARCHITECTURE PLANNING INTERIORS REES PLAZA AT EAST WHARF 9211 LAKE HEFNER PARKWAY, SUITE 300 OKLAHOMA CITY, OKLAHOMA 73120 P: 405.942.7337 F: 405.948.1261

Mechanical Engineer 050 Engineering Company 228 Robert S. Kerr Ave, Suite 515 Oklahoma City, OK 73102 P: 405.236.2030 F: 405.239.6101

Electrical Engineer

Horner Associates Engineers, Inc.

1306 Commerce Drive Norman, OK 73071 P: 405.801.2528 F: 405.801.2529 Civil Engineer

MacArthur Associated Consultants

3033 NW 63rd St., Ste. 250E Oklahoma City, OK 73116 P: 405.848.2471 F: 405.848.2474 Structural Engineer Zahl-Ford, inc. 8411 S. Walker

Oklahoma City, OK 73139 P: 405.634.3393 F: 405.634.6414

100% SUBMITTAL DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION MIKE MONRONEY AERONAUTICAL CENTER - OKLAHOMA CITY, OKLAHOMA

TELECOMMUNICATIONS PLAN

PSL - POWER SERVICES LABORATORY

Construction Work Request No: 09-018745

REPARED BY Rees Associates

Horner Associates Engineers, Inc.

1306 Commerce Dr. Norman, OK 73071
Certificate of Authorization No. CA 3520, Expires 6/30/2011

COPYRIGHT © 2011 HORNER ASSOCIATES ENGINEERS, INC. ALL RIGHTS RESERVED

info@haeinc.com Ph (405) 801-2528 Fax (405) 801-2529

Jon Berkman

May 26, 2011 T-301

ISSUED BY OFFICE OF BLP FACILITY MANAGEMENT DRAWING NO. AMP-400 08-008257