

DATE: December 22, 2011

SUBJECT: **Addendum No. Five** to the Specifications and Drawings for the **Multi-Purpose Building Restroom Renovation**
Federal Aviation Administration, Mike Monroney Aeronautical Center, Oklahoma City, Oklahoma

This Addendum modifies and takes precedence over the original Specifications and Drawings and forms a part of the contract documents.

CLARIFICATIONS:

1. Question: I was reading the Clarifications contained in Amendment 3, dated 12/19/2011. Clarification #14 contained the following statement: "Answer: All restrooms will have speakers; additional information pending." How does this statement affect the proposal due date, with additional information forthcoming but not yet issued?

Answer: **All restrooms will have new ceiling mounted public address speakers and new wiring to the nearest existing connection(s) to the building P/A system. Speakers shall be AudioMaster Model AMR6-2570K (70 Wrms) by Federal Signal Corporation, or approved equal. Existing P/A speakers within restrooms are to be removed and discarded.**

Proposal due date will not be extended.

Further clarification to Question 2, Addendum Four:

2. Question: Can you please provide a height AFF for the Accent pattern in the FRP? This is strictly to determine whether or not the sheets will be cut.

Answer: The precise height of the accent is a function of the manufacturer's tile pattern (emulating 4"x4" tiles): the wall should appear to be constructed of whole tiles (except as trimmed vertically at adjacent walls). The top of the accent band should be above the top of the toilet partitions, and below the top of the mirrors. The panels can be manufactured with the indicated accent band, and the standard panel height is 8 feet. Given that the finished ceiling height is 8 feet, and the presence of the porcelain tile base, the panels should be continuous from the base trim to above the finish ceiling. There will be a horizontal joint in the panels at the light cove, which will be concealed by the egg crate diffuser. Refer to section detail C/4. **The anticipated colors for the Marlite Symmetrix FRP panels are a "C118G44 Almond" field, with "C131G44 Everglade" accent. Final color selection is subject to change pending receipt and approval of all submittals.**