

	BASE BUILDING SPACE ALLOCATION				
	ROOM FUNCTION	Allowable Space per Staff	Final Validated		Allowable Space
			Max Shift Count	New ATCT / TRACON Staffing	
3RD FLOOR	Terminal Manager	180	2	2	360
	Staff Manager	144	1	1	144
	ATCT Operations Manager	144		1	144
	ATCT Operations Supervisor	96	5	7	480
	ATCT Staff Specialist & Support	68		3	204
	Administrative Officer	96	2	2	192
	Admin Assistant	96	1	1	96
	ATCT Support Manager	96		1	96
	Secretary	96	0	1	96
	Contractors	68	6	6	408
	Tower Simulation System (TSS) Area				
	Simulation Lab	req			625
	CBI/Classroom	req			375
	Prebrief/Debrief	req			100
	Office	req			100
	ETG Lab	req			500
					3920
	Tech Ops District Manager	180	1	1	180
	Tech Ops SSC Manager	144	2	2	288
	Administrative Coordinator	96	2	2	192
	Coordinator	96	2	2	192
	IT Support (contractor)	96		1	96
	On-Site ATSS (TID)	96	2		192
					1140
	Mail Room / Files / Copy Area	req			350
	Administrative Storage	req			350
	CBI Training Room	req			650
	Large Conference Room	req			800
	Small Conference Room	req			400
	Janitor Closet	req			60
					2610

3	TRACON Operations Manager	144		3	432
	TRACON Operations Supervisor	96	5	9	480
	Traffic Management Officer	96	1	1	96
	Traffic Management Supervisor	80	2	2	160
	Traffic Management Coordinator	68	6	11	408

2ND FLOOR

TRACON Staff Specialist & Support	68		4	272
TRACON Support Manager	96		2	192
Terminal Control Specialist	0	76	111	0
Contract Weather Observers	96	2	7	192
Tape Play-Back	req			175
Debriefing Room	req			200
Drug Test Room	req			80
TRACON	req			3,000
Locker Room	req			800
Break Room/Kitchen	req			1,400
Shower Area	2@60			120
				8007

1ST FLOOR

SS-Systems Specialist	96	2	2	192
On-Site ATSS	96	9		864
Electronics Equipment Room(s)	req			4,000
TELCO	req			475
Logistics	req			150
Storage	req			1,200
Technical Library	req			450
LAN Room/Security Equipment	req			100
				7431
On-Site ATSS (Env)	96	3		288
E/G Room	req			1,200
Electrical Switchgear Room	req			1,900
UPS Room	req			500
Battery Room	req			600
Mechanical Equipment Areas	req			5,000
Technical Work Space	req			500
Environmental Shop	req			600
DDC/Fire/Power/RMM Control Room	req			150
Loading Dock/Shipping/Receiving	req			275
				11,013
Security Guards	0	4	10	0
Security Area	req			250
				250

Smoking Room	req			100
20% Planning Factor (restrooms/corridors, etc.)	req			6,817
				6917

[illegible]

[illegible]