

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE	PAGE 1	OF PAGES 4
2. AMENDMENT/MODIFICATION NO. 0001		3. EFFECTIVE DATE 07/12/2010		4. REQUISITION/PURCHASE REQ. NO. SO-10-01879		5. PROJECT NO. (If applicable)
6. ISSUED BY DOT/FEDERAL AVIATION ADMINISTRATION SOUTHER REGION, ASO-52 1701 COLUMBIA AVENUE COLLEGE PARK, GA 30337				7. ADMINISTARTED BY (If other than Item 6) DOT/FEDERAL AVIATION ADMINISTRATION SOUTHER REGION, ASO-52 1701 COLUMBIA AVENUE COLLEGE PARK, GA 30337		
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code) All Prospective Offerors.				<input checked="" type="checkbox"/>	9A. AMENDMENT OF SOLICITATION NO. DTFASO-10-R-00121	
					9B. DATED (SEE ITEM 11) 06/17/2010	
				<input type="checkbox"/>	10A. MODIFICATION OF CONTRACT/ORDER NO. 0001	
*TO BE COMPLETED BY VENDOR IF NOT COMPLETE					10B. DATED (SEE ITEM 13) 07/12/2010	
CODE		FACILITY CODE				

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☐ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer is ☐ extended ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation on as amended, by one of the following methods:

(a) By completing Item 8 and 15, and returning 1 copies of the amendment; (b) acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hours and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

<input type="checkbox"/>	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT/ORDER NO. IN ITEM 10A.
<input checked="" type="checkbox"/>	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14.
<input type="checkbox"/>	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
<input type="checkbox"/>	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☒ is not, ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

RE: DTFASO-10-R-00121 – HKS ATCT Fire Protection and Life Safety Modifications, Hawkins Field Airport Jackson, Mississippi.

This modification is created to include a summary of the locations for the Asbestos - Containing - Material (ACM) prepared by Research Management Consultants Inc; not included in Appendix 6 of the solicitation.

No Other Changes.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING SPECIALIST (Type or print) Hector L De Jesus	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED 07/12/2010
(Signature of person authorized to sign)		BY  (Signature of Contract Specialist)	

1.8 INSPECTION SUMMARY

The following ACM was identified in the Jackson Hawkins Field ATCT (all quantities are approximate):

FIRST FLOOR

- Electronic Equipment Room
 - 220 sq ft of 9 in x 9 in white/grey streaked floor tile and mastic
 - window caulk (wherever present on windows)
 - fire door insulation (not sampled to avoid damage; assume ACM)
- Entry (Lobby)
 - 140 sq ft of 9 in x 9 in white/grey streaked floor tile and mastic
 - fire door insulation (not sampled to avoid damage; assume ACM)
- TELCO
 - fire door insulation (not sampled to avoid damage; assume ACM)

SECOND FLOOR

- AT Chief's Office
 - 210 sq ft of 9 in x 9 in white/grey streaked floor tile and mastic (under carpet)
 - fire door insulation (not sampled to avoid damage; assume ACM)
 - window caulk (wherever present on windows)
- Cable Chase
 - inaccessible; assume ACM
- Lavatory
 - 28 sq ft of 9 in x 9 in white/grey floor tile and mastic
 - fire door insulation (not sampled to avoid damage; assume ACM)
- Stair
 - window caulk (wherever present on windows)

1.8 INSPECTION SUMMARY (continued)...all quantities are approximate

THIRD FLOOR

- Breakroom

- 200 sq ft of 9 in x 9 in white/grey streaked floor tile and mastic
- window caulk (wherever present on windows)
- fire door insulation (not sampled to avoid damage; assume ACM)

- Cable Chase

- inaccessible; assume ACM

- Stair

- window caulk (wherever present on windows)

- Storage

- fire door insulation (not sampled to avoid damage; assume ACM)

FOURTH FLOOR

- Lavatory

- 36 sq ft of 9 in x 9 in white/grey streaked floor tile and mastic
- window caulk (wherever present on windows)
- fire door insulation (not sampled to avoid damage; assume ACM)

- Mechanical Room

- 180 sq ft of 9 in x 9 in white/grey floor tile and mastic
- grey HVAC caulk (wherever present on HVAC duct seams)
- fire door insulation (not sampled to avoid damage; assume ACM)

- Stair

- 12 sq ft of 9 in x 9 in white/grey streaked floor tile and mastic (landing only)

- Stair to Cab

- 8 sq ft of 9 in x 9 in white/grey streaked floor tile and mastic (landing only)
- cementitious wall panel (quantity included with control cab)

1.8 INSPECTION SUMMARY (continued)...all quantities are approximate

- Storage

- drywall joint compound (wherever present)
- fire door insulation (not sampled to avoid damage; assume ACM)

FIFTH FLOOR

- Control Cab

- 200 sq ft of cementitious wall panel (quantity includes stair to cab)
- 8 sq ft of foil backing with tar (located on top of roof hatch door)

- Control Cab Roof

- roof flashing materials (wherever present at roof seams, corners, etc.)
- roof mastic (wherever present)

- Exterior

- exterior caulk (wherever present at windows, seams, penetrations, etc.)
- window putty (wherever present on windows)