


GENERAL NOTES:

1. PRIOR TO START OF WORK, ALL NECESSARY MEASURES SHALL BE TAKEN BY THE CONTRACTOR TO PROTECT ALL THE EQUIPMENT INSIDE THE RADAR EQUIPMENT ROOM.
2. SPECIAL CARE SHALL ALSO BE TAKEN TO PROTECT THE CORRIDOR WALLS AND CARPETS FROM GETTING SCRATCHED AND/OR SOILED WHEN TRANSPORTING CONSTRUCTION MATERIALS AND TOOLS INSIDE AND OUTSIDE THE BUILDING.
3. DUE TO THE SENSITIVITY OF THE RADAR EQUIPMENT INSIDE THE BUILDING, THE CONTRACTOR WILL NOT BE PERMITTED TO UTILIZE ANY ELECTRICAL WALL OUTLETS OR ANY POWER SOURCE INSIDE THE BUILDING WITHOUT THE APPROVAL OF THE RESIDENT ENGINEER.
4. INSTALLATION OF VINYL TILES SHALL BE STRICTLY IN ACCORDANCE WITH THE RECOMMENDATION OF THE MANUFACTURER.
5. RADAR ROOM, ADJACENT ROOMS AND CORRIDORS SHALL BE PROPERLY VENTILATED DURING VINYL TILES INSTALLATION.

SCOPE OF WORK

1. REMOVAL AND DISPOSAL OF THE TWO LAYERS OF FLOOR CARPET AND PLYWOOD IN THE RADAR EQUIPMENT ROOM AND REPLACE IT WITH:  
VINYL TILES BY ARMSTRONG CO.  
MODEL: \*51860031  
COLOR: SOFT COOL GRAY  
NOTE: SUBMIT SAMPLE FOR APPROVAL.
2. REMOVAL AND DISPOSAL OF THE RADAR EQUIPMENT ROOM PERIMETER WALL BASEBOARDS. REPLACEMENT SHALL BE OF THE SAME SIZE AS THE EXISTING AND THE SAME COLOR AS THE VINYL TILES.  
NOTE: SUBMIT SAMPLE FOR APPROVAL.
3. REWORK AND PAINT THE WALL OPENINGS LOCATED ON THE WEST AND SOUTH WALL OF THE RADAR EQUIPMENT ROOM. FIELD VERIFY.
4. CLEAN AND PAINT MOLDS CONTAMINATED WALLS IN THE EQUIPMENT ANNEX ROOM, RADAR EQUIPMENT ROOM, AND TELCO ROOM. FIELD VERIFY.

PLAN - BUILDING 408  
SCALE: 1/8" = 1'-0"



REV	APPROVED DATE	DESCRIPTION	JCN	REDLINE DATE	APVD
DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION ATO - TECHNICAL OPERATIONS WESTERN SERVICE AREA ARSR JOINT SURVEILLANCE SYSTEM, BLDG 408 CARPET REPLACEMENT IN THE RADAR EQUIPMENT ROOM MILL VALLEY					
REVIEWED BY	SUBMITTED BY	DO NOT SIGN	DO NOT SIGN	DO NOT SIGN	DO NOT SIGN
	MAX LIBAO	DO NOT SIGN	DO NOT SIGN	DO NOT SIGN	DO NOT SIGN
	PROJECT ENGINEER	DO NOT SIGN	DO NOT SIGN	DO NOT SIGN	DO NOT SIGN
	DESIGNED	ML	ISSUED BY	DATE	JCN
	DRAWN	RCL	ENGINEERING SERVICES	07/21/2011	700341
	CHECKED	ML	INFRASTRUCTURE	DRAWING NO	REV
				QMV-D-ARSR-C001	