

**SCOPE OF WORK – Contaminated Carpet at ARSR  
Mill Valley, California**

- 1. Removal and disposal of the two layers of floor carpets and plywood in the radar equipment room (Room No. 15 & 16). The radar equipment room is approx. 2100 sq. ft.**
- 2. Removal and disposal of the perimeter wall baseboards in the radar equipment room. The perimeter wall is approx. 200 lin. ft.**
- 3. After removal of carpet in the radar equipment room, the floor shall be cleaned.**
- 4. Installation of 12” x 12” vinyl floor tiles in the radar equipment room.**
- 5. Installation of the perimeter wall baseboards in the radar equipment room.**
- 6. The recently closed two wall openings, where rain water is seeping, using concrete blocks need to be rework and refinish due to poor workmanship.**
- 7. Cleaning and repainting of molds contaminated walls in Room No. 12 & Equipment Annex, wall height is approx. 8 ft and Room No. 15 & 16, wall height is approx. 10 ft.**