SECTION 01710 CLEANING

PART 1 - GENERAL

1.1 SUMMARY

The scope of this project will be performed in a partially occupied special use environment. Daily cleaning and protection shall be a requirement. All prospective bidders are encouraged to visit the project site to ascertain the criticality of maintaining a clean litter free environment.

A. Requirements Included.

- 1. Execute cleaning during the progress of work. This includes but not limited to the following:
 - a) Remove waste packaging and waste construction material.
 - b) Remove temporary protective covers and barriers at the end of each shift.
- 2. Execute cleaning for final inspection.
- 3. Execute cleaning at completion of the work.

1.2 RELATED REQUIREMENTS

Section 01651: Materials and Equipment Section 01800: Contract Closeout.

1.3 PRODUCTS

A. <u>Materials</u>. - Use only those cleaning materials recommended by the manufacturers of the surface being cleaned so as not to create hazards to health or property.

1-4 EXECUTION

A. <u>Disposal Requirements</u>. - Conduct cleaning and disposal operations to comply with codes, ordinances, regulations, and anti-pollution laws.

B. Final Cleaning.

- 1. Employ skilled workmen for final cleaning.
- 2. Remove grease, mastic, adhesive, dust, dirt, stains, fingerprints, labels, and other foreign materials from visible interior and exterior surfaces.
- 3. Ventilating system:
- 4. Clean permanent filters and replace disposable filters if units were operated during construction. Do not operate blowers and coils without filters during construction.
- 5. Broom clean exterior paved surfaces, repair damaged sod areas with sod and rake. Clean other surfaces of the grounds.
- 6. Prior to final completion. Contractor shall conduct an inspection of interior and exterior surfaces, and all work areas to verify that the entire work is clean.
- C. <u>During Construction</u>. Maintain all areas under Contractor's control free of extraneous debris. Conduct a specific maintenance program to prevent accumulation of debris at the construction site, storage and parking areas, and along access roads and haul routes.

CLEANING 01710-1

- D. ARTCC Operational Areas. Clean up after each work shift.
- E. <u>Debris Collection</u>. Provide containers for debris deposit and schedule periodic collections and disposal of debris. Provide additional collections whenever the periodic schedule is inadequate to prevent accumulation.

END OF SECTION 01710

* * * * *

CLEANING 01710-2